



Capital Projects & Purchasing Department
113 Mable T. Willis Blvd.
Walterboro, SC 29488
843.539.1968

BID: SW-25
Colleton County C&D Landfill Improvements

DUE: Thursday, September 27, 2018 at 11:00am

Addendum #3
dated 9-25-2018

The following questions have been submitted for clarification:

- 1) Will a Bid Bond be required? **Answer:** Yes, a bid bond for 5% of the bid price is required. This can be in the form of a surety bond or certified check.
- 2) Are Performance and Payment Bonds required? **Answer:** The requirement for the 100% of contract price Performance and Payment Bond is hereby removed.
- 3) Is there a spec for the Borrow Material line item? **Answer:** Borrow material shall be a sand clay material similar to the current fill material observed during the site visit. Borrow material is not top soil.
- 4) Is there a spec for the Graded Aggregate Base Course? **Answer:** This line item shall be a well graded aggregate per SCDOT spec. (i.e. FLBC-limestone or MBC-granite)
- 5) Is there a spec for the Rip-Rap? **Answer:** Class B.
- 6) Are compaction tests required on the slopes after fill is placed? **Answer:** No.
- 7) Where is the sodding to be placed? **Answer:** This is to be placed at the inlet to the slope drains.
- 8) Is the HDPE to be single wall or double wall? **Answer:** Single wall.
- 9) Is there a spec for the 15" HDPE Grate Inlet? **Answer:** This item is hereby removed from the bid. See new bid tab.

*Attached is the revised bid tab.

*Attached is the mandatory pre-bid sign-in sheet from September 20, 2018.

G. BID FORMS

BID FORM				
BID NUMBER:	SW-25			
	Colleton County C&D Landfill Improvements			
OPENING DATE & TIME:	September 27, 2018 @ 11:00am			
OPENING LOCATION:	Capital Projects & Purchasing Dept.			
	113 Mable T. Willis Blvd.			
	Walterboro, SC 29488			
	Quantity	Unit	Unit Price	Total
MOBILIZATION	1	LS	\$	\$
UNCLASSIFIED EXCAVATION	3385	CY	\$	\$
FINE GRADING	22150	SY	\$	\$
GRADED AGGREGATE BASE COURSE	750	TON	\$	\$
BORROW MATERIAL	1500	CY	\$	\$
15" HDPE PIPE	560	LF	\$	\$
RIP-RAP	125	TON	\$	\$
GEOTEXTILE FABRIC - UNDER RIP-RAP	75	SY	\$	\$
EROSION CONTROL MATTING - SINGLE NET STRAW (TYP)	22150	SY	\$	\$
SODDING - BERMUDA	275	SY	\$	\$
PERMANENT GRASSING - SCDOT FALL/WINTER MIX	5	ACRE	\$	\$
CONTRACTOR'S TOTAL BID =				\$
CONTRACTOR NAME: _____				
SIGNATURE: _____		TITLE: _____		
PRINT NAME: _____		DATE: _____		
UNCLASSIFIED EXCAVATION - Line item to include sideslopes(where necessary) as well as ditch cleaning/shaping.				
FINE GRADING - Grading of all working slopes, grading of landfill top, ditch grading, and roadway grading.				
GRADED AGGREGATE BASE COURSE - Line item to include material, hauling, and placement on perimeter roadway.				
BORROW MATERIAL - Typical sand clay for sideslopes. Must be approved by engineer prior to placement. Material to be placed in 6" lifts for a total of 2' for landfill debris cover. Line item to include material, hauling, and placement.				
15" HDPE PIPE - Line item to be used in four locations for proposed slope drainage. See typical in "I. - Project Information".				
<u>By signing this Bid Form, the BIDDER acknowledges that he/she has read this document and understands the provisions, agrees to be bound by its terms and conditions, will adhere to scheduling requirements stated herein and is capable of providing all required products and/or services.</u>				

THIS PAGE MUST BE COMPLETED AND SUBMITTED AS A PART OF YOUR BID

